

40m upgarde plan scrutiny

Koji Arai / Yoichi Aso / Rana Adhikari

Rev. A: 2009/08/22

Rev. B: 2009/09/22

Rev. C: 2009/09/29

40m upgarde plan scrutiny

- **Purpose**
- **People**
- **Task list up**

By category ~ What has been done / what should be done

- Interferometer design
- Optics
- Electronics
- Mechanics
- Digital control

By development phase

- Time Line

Reference:

**LIGO-T080074-00-R
40m upgarde Wiki**

Purpose of the upgrade

Demonstration of the AdvLIGO interferometer technologies

- Prototyping of AdvLIGO LSC

Lock acquisition

"Prove AdvLIGO LSC actually works"

Green laser locking

"Realize lock of the arms independently from the main beam"

"Achieve semi-deterministic lock & smooth handing off"

Noise mechanisms / DC readout

"Discover and/or confirm by a model RSE specific noise couplings"

- Tuned / Detuned RSE comparison

"Address advantage and disadv. of the tuned/detuned configuration"

"Demonstrate smooth transition"

- RGC based digital control system

"Demonstrate complicated LSC code on the connected multiple systems"

"Establish rapid prototyping methods with simulated plants on the processors"

Purpose of the upgrade

To do anything useful to make the AdvLIGO easier / faster

- DC&Dither technologies

Offset lock and handoffs

AF WFS technique

"Develop and characterize various new useful techniques"

- Interferometer Diagnosis

Cavity characterization using aux. laser injection

"Provide a method of precise in-situ characterization of the interferometer"

- Development / test bench of advanced technologies

GigE CCD WFS technique

Adaptive noise cancellation

"Demonstrate how it works"

"Understand and improve its limitations"

People

Alan	Supervising
Rana	Supervising / Project control / (adaptive)
Steve	Vacuum / Purchasing / Mechanics
Bob	Vacuum
Koji	Project control / Optics / Electronics / Mechanics / Digital
Peter	Digital control / Locking / LSC
Joe	Digital control / Computing / (phase camera)
Alberto	Electronics / Locking / LSC / noise
Jenne	Mechanics / Optics / Electronics / (adaptive)
Kiwamu	Optics / Electronics / Locking / LSC / noise
Aidan	Green lock planning / installation
David	Green lock planning / installation
Zach	Mechanics / Installation assistance

Category-wise task list up

Interferometer design

- **"Done" (or decided)**

Interferometer design

AdvLIGO like optical configuration

Same level arm finesse ($F \sim 450$) => main concern: test of central part

PR gain decided for carrier, SR gain decided by sensitivity

Small asymmetry, extraction of f_2 by a undercoupled SEC

=> good through put of f_2 to the dark port

Use of PRTT1 Trans as POP

Put less importance on WFS

No change in MC => fine tuning of mod freq. will be necessary

- **"To Do"**

Revisiting the optical parameters

Summarize power budget and resonant conditions in the cavities

Compare with current finesse / loss / reflectance (coupling)

Current recycling gain ~ 6.3 -> $R_{com} = 86\%$, loss?

Summarizing lock acquisition / signal extraction scheme

Make diagrams

Tuned or detuned?

Tuned / offset detuning

What should be compared?

Optics / Optical layout

- "Done"

Main Optics order

ITM2+2 / PRM1+1 / SRM1+1

Polisher: Coastline Optics

Coater: ATF

Repolish of ITMs (+2weeks)
Coating (3weeks)

Detailed optical layout in vacuum

- "To Do"

Checking specs of the mirrors / lenses in the vacuum

Making optical layouts of the tables / Update the table layout

Specs of the folding mirrors to be investigated and purchased

Specs of the MMT mirrors to be investigated and purchased (see next page)

Specs of various aux mirrors and mounts in vacuum

General on table mirrors and mounts

Check unfavorable optics on the PSL table

Quoting & order of ETMs

Specs for the green

Optics / Optical layout

- **"To Do" (cont'd)**

- Consideration of the effect of the wedge angles**

- Wedge deflection design

- Blank wedge plates for installation?

- Schedule some tasks**

- Realignment of MC to have beams centered on the mirrors

- Mirror wiping of the current FP mirrors ~ ask suggestions of Bob

- Optics characterization with GariLynn for mirror metrology

Optics ~ PSL table layout

- "To Do"

Possible PSL replacement by 2W innolight

Need detailed design of the PSL table

Reference Cavity after the PMC?

Upgrade of the intensity stabilization

(Optics/Electronics)

Green injection

- "On going"

Fiber noise cancellation experiment
SHG phase noise measurement

- "To Do"

Deciding the ETM specs

Revisit the green frequency noise spec
Decide finesse of the cavity (~50?)
Ask for the new substrate / coating

Making detailed design of the transmission tables

Mode matching / alignment procedure
Table layout / Optical components and mounts
Need lasers? Need new tables and enclosures?

Detailed consideration of handing off from green to IR

RGC implementation

Electronics

- **"Done"**

Multiplier circuit quote

Prototype triple resonant modulator

- **"To Do"**

Making detailed diagrams for the detection chain

Modulation / Detection / Demodulation

Fabrication of modulation electronics

Modulation electronics assembly & test

Triple freq modulator (detailed test & finalization)

Fabrication of detection electronics

Fabrication of the resonant PDs (11MHz/33MHz/55MHz / DD PDs?)

Demodulator (single / double)

Mechanics

- **"To Do"**

MMT mechanics design&fabrication

Extend bases?

How to actuate the length?

Mode matching procedure?

Passive TT development

Basic test (f_{res} , Q)

Isolation test?

Mounts for the in-vac mirrors

Installation assistance jigs (x3)

To record and point the spot position in the vac chamber

Should have the same foot print as the SOS

SOSs (x2)

Check with Steve

Preparations (clean? bake?)

Digital control system

- **"Done"**

RGC code running on megatron (with ADC/DAC or with SHM)

Interface blocks from ADC to AA/AI connectors under development

- **"To Do"**

Detailed plan for the upgraded system

- List up needed components

- Design LSC codes

- Development of new EPICS panels

Single machine test ~ integration of RFM

- Stand alone test / Connection test

- Cavity control test

Multiple machine test

- Simple test with one FP?

- (suspension control / cavity lock / alignment script)

Full system upgrade

Mode spacing measurement

- **"Done"**

- Demonstration for the arm cavities**

- FSR measurement

- Cavity g-factor measurement

- Characterization for the SRC/SEC on going.**

- **"To Do"**

- Measurements for the new PRC/SEC**

- Measurements for the asymmetry / BS branching ratio**

- Reflect the info to the fine adjustment

- Measurements for the new arm cavities**

Miscellaneous

- "To Do"

Cleaning of the cabling?

Optical lever?

Upgrade of the console desk?

Milestone oriented task listing

Development phases

Preinstallation preparation (~XX/XX/2009)

Test with the current configuration

Purchasing Optics / Mechanical design / Electronics preparations

Digital control

Installation (XX/XX/2009~XX/XX/2010)

Works in vacuum chambers / Works on the tables

Electronics preparations / Digital control

Phase1 experiment (XX/XX/2010~XX/XX/2010)

DRMI investigation

(Full lock achievement)

Phase2 experiment (XX/XX/2010~XX/XX/2011)

ETM replacement

green laser installation / locking

Full lock achievement

Preinstallation preparation (~XX/XX/2009)

- Non-invasive works

[IFO design] revisit optical parameters / Comparison with the current meas.

[IFO design] summarize lock acq. / signal extraction scheme

[Optics] check specs in-vac optics / order

[Optics] making/updating optical layouts of the tables

[Optics] check unfavorable optics on the PSL table

[Optics/Green] decide ETMs specs / order ETMs

[Optics] check wedge effects / consider blank wedge plate

[Optics] new main optics inspection / characterization

[Mechanics] MMT mechanics design / fabrication

[Mechanics] passive TT development (fabrication / basic test / further test?)

[Mechanics] order in-vac mounts

[Mechanics] check SOSs / Assembling

[Mechanics] installation-jig design / fabrication

[Electronics] detailed diagrams

[Electronics] detection electronics (PD/Demod/Modulation electronics)

[Electronics] multiple resonant EOM

[Digital] detailed planning / hardware preparations

[Digital] single machine RFM test

[Green] SHG / Fiber noise experiment at Bridge lab.

Preinstallation preparation (~XX/XX/2009)

- Invasive works

[Digital] single machine cavity test / multiple machine tests

[Digital] multiple machine tests

[Optics] MC realignment

[Optics] mirror wiping experiment

- Invasive work on the PSL table

Mach Zehnder removal / EOM placement & modulation check

Unfavorable optics replacement (periscope, etc)

MC lock confirmation

Laser replacement / intensity stab (after the vent)

Installation (XX/XX/2009~XX/XX/2010)

[Digital] Full system upgrade (before the installation? after?)

[Green] Detailed design of the transmission tables

[Green] Detailed consideration of handing off from green to IR

Installation procedure

- Work in the vacuum chambers

Removal of PRM/SEM/ITM/MM

Spec check for existing optics, if necessary

MC output mode ~ beam scan

Rough estimation of MM telescope length

MMT placement

MMT output mode ~ beam scanning / adjustment

PRC Folding Mirror TT placement

Hit both ETM center

- need PRM wedge correction

- jig+dummy wedge simulator (1064AR coat?) x 3

PO ports alignment (need a pilot beam???)

Some facts & ideas

- there is no gate valves
- very weak trans. through MC even for P pol
- use very weak S pol resonance
- align beams without ITMs
- correct ITM wedge with dummy optics
- hit the center of ETMs (use a target plate with hole)
- put ITMs
- use script to find first fringes

Installation (XX/XX/2009~XX/XX/2010)

- Work in the vacuum chambers (cont'd)

ITMx2/PRM/SEM placement / cabling / damping control

Michelson Fringe

SEM folding placement

OMMT/OMC (lock & mode matching)

SEM placement

SEM placement / alignment

Out-vac alignment / Optical lever adjustment / pointing record

Vacuum work completed -> evacuation

- Post installation adjustments

Coarse alignment / fringes?

FP arm lock / IMMT tuning

OMC lock / OMMT tuning?

Phase1 experiment (XX/XX/2010~XX/XX/2010)

DRMI investigations

[Commissioning] TBD

Full lock achievement if possible

[Abs Length] Abs length measurements for the arm cavities/PRC/SEC

[IFO design / Green] new ETM optics inspection

[Green] Transmission table construction

Phase2 experiment (XX/XX/2010~XX/XX/2011)

ETM replacement

[Commissioning] TBD

Green laser installation / locking

[Green] Handing off from green to IR ~ RGC implementation

Full lock achievement


[IFO design] Tuned / detuned comparison

Time line

Time line

Preinstallation

IFO Design



Installation

Laser replacement

MC realignment

[Optics] Laser Replacement??

[Optics] MC realignment

- Invasive work on the PSL table

Mach Zehnder removal / EOM placement & modulation check

Unfavorable optics replacement (periscope, etc)

MC lock confirmation

Installation procedure

- Work in the vacuum chambers

Removal of PRM/SEM/ITM/MM

Spec check for existing optics, if necessary

MC output mode ~ beam scan

Rough estimation of MM telescope length

MMT placement

MMT output mode ~ beam scanning / adjustment

PRC Folding Mirror TT placement

Hit both ETM center

- need PRM wedge correction

- jig+dummy wedge simulator (1064AR coat?) x 3

PO ports alignment (need a pilot beam???)

- Work in the vacuum chambers (cont'd)

ITMx2/PRM/SEM placement / cabling / damping control

Michelson Fringe

SEM folding placement

OMMT/OMC (lock & mode matching)

SEM placement

SEM placement / alignment

Out-vac alignment / Optical lever adjustment / pointing record

Vacuum work completed -> evacuation

- Post installation adjustments

Coarse alignment / fringes?

FP arm lock / IMMT tuning

OMC lock / OMMT tuning?

Phase 1

Phase 2


ETM
inspection




Time line

Preinstallation


Detection
Electronics
Multiple
Resonant
EOM



Digital Control



Installation



Phase 1

Phase 2

DRMI investigations
[Commissioning] TBD

Full lock achievement if possible
[Abs Length] Abs length measurements for the arm cavities/PRC/SEC

ETM replacement
[Commissioning] TBD

Green laser installation / locking
[Green] Handing off from green to IR ~ RGC implementation

Full lock achievement
[IFO design] Tuned / detuned comparison

Full System Installation

ETM delivery

Install preparation

Green Installation & commissioning

In short ...

Lots of work still left

Optics (in vacuo, PSL), Mechanics, Digital system

Some electronics

Plan of green injections for long term

Vent 1 (small): for mirror wiping

To see whether we can improve the finesse or not.

Late Nov / Early Dec?

Vent 2 (big):

Laser replacement

Before the 2nd vent?

Full install of the new digital system

After the mirror installation

Tasks for now ~ as of 30 Sept 2009

- Rana: Ask Bram for the TT, Arrange 2W laser purchasing
- Steve / Bob: Help us as usual
- Koji: Review optical system towards purchasing
- Joe: Plan new digital system / diagram
- Peter: Let RFM working on megatron
- Rob: Give us various inputs!
- Alberto: Plan new LSC / diagram
- Jenny: Check SOSs with Steve & MMT design
- Kiwamu: Design works on the PSL table
- Aidan/David: Plan for the green injection
- Zach: Make the current PSL table photo/diagram
(and for the other tables too!)